

TOWN OF SCHODACK
RENSSELAER COUNTY, NEW YORK

SEWER DISTRICT NO. 5 – ULTRAVIOLET DISINFECTION

ADDENDUM NO. 2

May 2, 2024

TO THE BIDDERS:

The changes presented and/or attached hereto shall be made in the Contract Documents. This Addendum is intended to delete, add to, or clarify these specifications and/or Contract Documents.

CLARIFICATIONS

1. The following information for the existing Orenco control panel and modem is attached hereto: Orenco panel wiring diagram, ultrasonic level equipment cut sheet, and panel photographs.
2. The Contractor is responsible for coordinating the provision of panels. The design intent is that the Contractor coordinate and provide outside monitoring through a single communication connection for both equipment that is monitored now and equipment added under this contract.
3. The engineer is not aware of any special disposal requirements of materials from the former sand filter.
4. For any required bypass, the maximum estimated discharge flow is fifty (50) gallons per minute. It is not the intention to shut down the facility.
5. The Contractor may sample effluent from the second ultraviolet chamber, downstream of its weir and just before discharge from the chamber.
6. The steel cabinet shall be Hallowell 400 Series Commercial Storage cabinet, or equal (gray, 48"x18"x72", adjustable shelving, 200-pound capacity per shelf, multi-point locking with chrome locking handle, 2 year warranty).

CHANGES TO PLANS

1. **ADD** a note to Contract Drawing Sheet 5, "Enclosure Pad and Foundation (Item 6)" as follows: "NOTE: Under the slab, the Contractor shall provide a compacted layer of Type 2 subbase (Item 39), twelve (12) inches thick. The footing will bear directly on leveled and compacted subgrade, unless existing soil conditions require otherwise".

J:\2023053\CONTRACT\ADDENDA\ADD.2_05-02-2024.DOC